

Naples Park Infrastructure Improvements

October 9, 2018

Dear Residents/Business Owners of 95th Avenue North:

The Collier County Public Utilities Project Team is informing you that the entire length of the 95th Avenue water main will be installed between Vanderbilt Drive and US41, instead of one block at a time as originally planned. The change is needed because of the unusually high underground water table which makes construction of the deep underground stormwater and wastewater pipes very difficult. Excessive amounts of dewatering would be required which would overload the local stormwater system. Added benefits are: decreased potable water service interruptions, and getting all customers off of the failing asbestos-cement water main and onto the new water service earlier than planned. After the water main installation is complete (2-3 months) and the water table has subsided, work will resume block by block on the wastewater and stormwater systems as planned.

Things to know:

- Water main installation is the least disruptive part of the project because the pipes are relatively small. The water main will be located on the south side of the street requiring cuts to be made across driveways. Cuts will also be made across the street to service properties on the north side. Driveway cuts will occasionally be needed on the north side of the street.
- Existing concrete and asphalt driveways will be saw-cut along the water main alignment to ease removal. Paver driveways will have pavers removed in the water main alignment. During installation, driveways will be restored daily with compacted stone to ensure access. Following the water main installation of each block, the contractor will patch driveways with temporary pavement. Driveways will be fully restored following completion of the stormwater and wastewater phases of each block.
- The contractor will Hydroseed disrupted grassy areas and will water to ensure coverage. Permanent restoration of non-paved areas will occur following completion of the stormwater and wastewater phases of each block.
- Local traffic access will be maintained at all times.
- Construction of the water main on the 500 block has begun, anticipated to be complete by October 19, 2018.
- Construction of the water main on the 600 block is anticipated to begin approximately on October 15, 2018.
- Construction of the water main on the 700 block is anticipated to begin approximately on October 23, 2018.
- Construction of the water main on the 800 block is anticipated to begin approximately on November 5, 2018.
- The installation of the water main for each block will take approximately 2-3 weeks.
- During construction, notifications for planned water service outages will be sent to the affected residents; however, you may experience intermittent service outages due to field conditions and water main breaks.
- When construction of the water main is complete, the main will be flushed, pressure tested, and disinfected.
- Following satisfactory completion of testing and disinfection, the new services will be connected to individual homes and businesses.
- Construction will occur 7 a.m. to 7 p.m. Monday through Saturday.

Please contact our hot line at **239-269-1890** or email us at NaplesParkPUR@Stantec.com with any special concerns or access needs; our website will also provide updates and general information pertaining to the project as it progresses. <http://www.collierpur.com>

Cordially,

Collier County
Engineering and Project Management Division and Stormwater Section